

DH 11th FLOOR SCREEDING WORK								
(Existing Dharumavanta Hospital Building)								
Item	Description	Unit	QTY	RATE	LABOUR AMOUNT	RATE	MATERIAL AMOUNT	TOTAL AMOUNT
1	Bill NO: 1 <u>PRELIMINARIES</u>							
1.1	General Notes							
1)	Abbreviations							
	m - meter							
	No - numbers							
	m3 - cubic meter							
	m2 - square meter							
	Lm - Linear meter							
	t - tonnes							
	md - including							
	mm - millimeter							
	dia - diameter							
	SS - Stainless Steel							
	GI - Galvanised Iron							
1.2	<u>Site Management Costs</u>							
1.2.1	Allow for all on and off site management cost including costs of foreman and assistants, temporary services, hoardings and similar.	item	1					-
1.3	<u>Clean - up</u>							
1.3.1	Allow for clean - up of completed works and site upon completion.	item	1					-
TOTAL OF BILL NO. 01 (PRELIMINARIES) (CARRIED OVER TO THE GENERAL SUMMARY)								-
2.1	Bill No: 02 <u>SCREEDING WORKS</u> <u>GENERAL</u> (a) Rates shall include for: cleaning out cavities, forming rebated reveals and pointing and cleaning down to reveals where necessary; fractional size blocks, all necessary machine templates, reinforcement in walls and for all necessary making good (b) Rates shall include for providing approved quality mesh at joints between structural old members and new plastering from floor. (c) For screeding works manufactured sand shall be used. (d) Should use required chemicals to protect the exposed reinforcement. (e) Should use required chemicals to bond the old concrete and new concrete.							

Item	Description	Unit	QTY	RATE	LABOUR AMOUNT	RATE	MATERIAL AMOUNT	TOTAL AMOUNT
2.2	SCREEDING							
2.2.1	100mm Thick Chemical Cement Screeding using (ReCon GP) refer to the manufacturer instructions.	m ²	8.58					
	100mm Thick Chemical Cement Screeding using (MeggaAdd WL2) refer to the manufacturer instructions.	m ³	8.58					
TOTAL OF BILL NO. 02 (SELF LEVELING WORKS) (CARRIED OVER TO THE GENERAL SUMMARY)								-
Bill No: 03 FLOOR LEVELING								
3.1	SELF-LEVELING a) Rates shall include for: All necessary material & workmanship							
3.3	FLOOR SELF-LEVELING							
3.3.1	3mm Self leveling compound (IGMH provide material)	m ²	8.58					-
TOTAL OF BILL NO. 03 (FLOOR LEVELING) (CARRIED OVER TO THE GENERAL SUMMARY)								-
Bill No: 04 VINYL FLOORING								
4.1	General a) Rates shall include for: all labour in vinyl works, Glue & Proper tools to do the welding works (Exesting to New)							
4.2	Vinyl Flooring & Welding works							
4.2.1	Vinyl Flooring works	m ²	8.58					-
4.2.2	Vinyl Welding works	m	44.27					-
TOTAL OF BILL NO. 04 (VINYL FLOORING) (CARRIED OVER TO THE GENERAL SUMMARY)								-
Bill No: 05 ADDITIONS								
1.1	General All Additional Works	nos			-		-	-
	All Ommition Works	nos			-		-	-
TOTAL OF BILL NO. 05 (Additions) (CARRIED OVER TO THE GENERAL SUMMARY)								-

Note: All Materials to be Approved by IGMH